



Facility Upgrading at Fraser Surrey Docks

Fraser Surrey Docks is presently undergoing some major facility upgrades with five separate construction projects currently taking place on dock. We are making every effort to mitigate the impact these projects will have on our regular terminal activities and our regular dock users. Once completed, these projects will increase the efficiencies and capabilities of Fraser Surrey Docks. As always at Fraser Surrey Docks, the major focus for all five of these construction projects is safety. Please see below for a brief outline of the scope of each construction project and please ensure that you take extra caution when travelling near or around any of these projects.

- 1.) **Construction of the Agri Bulk Handling Facility** – Taking place in and around Shed 1, this project includes the digging of a belly-dump rail car pit, installation of receiving and reclaiming conveyors, mobile vessel loading equipment and converting Shed 1 into a agri bulk storage facility. This project will be completed in March 2011.
- 2.) **Berth Strengthening/Upgrading** – This construction is presently taking place at Berth 4 and will move down river to Berth 3 and 2 as the project continues. The scope of this project is to install sheet pile wall to protect the under-berth side slope thereby sustaining the strength of the berths. This project will be completed by March 2011.
- 3.) **Dock Strengthening** – Coinciding with project #2 (as described above), this project is focusing on strengthening the top side of the dock. The primary scope of the work is to remove and replace the asphalt and concrete where required the berth decking to increase the weight capacity of the berth. This project will be completed by January 2011.
- 4.) **Rail Line Replacement/Upgrading** – The general scope of this project is to remove and replace one of the major rail lines at Fraser Surrey Docks. This project will be carried out in two phases. The first phase will focus on the rail line adjacent to Shed 1 while the second phase will focus on a portion of the track between Shed 1 and the Main Security Kiosk. Each phase should take approximately two weeks each to complete pending good weather.
- 5.) **Container Yard Resurfacing Project** - Since the beginning of 2006, Fraser Surrey Docks has been undergoing a dramatic face-lift in the Container Yard. The six-phase project has aimed to replace the full depth pavement structure within the container yard. This year's portion will be the last phase of the project. The area to be resurfaced covers from the upriver end of Shed 5 to the Container Truck Gate, as well as the upriver ends of C and D lanes. The construction area will undergo a complete restoration of the asphalt tarmac. This phase is scheduled to be completed by the end of March 2011, pending weather as well.

Please see below for a map of the areas of the dock where these projects will take place.



We thank you for your continued patience during the construction of these projects as we continue our commitment to remaining the largest multipurpose facility on the West Coast of North America, now and in the future

Thank You,

Fraser Surrey Docks